NOTICE TO CONTRACTORS

THIS IS A LIST OF SPECIFIC REQUIREMENTS FOR STREET OPENINGS.AND ENCROACHMENTS, INCLUDING CURB OR SIDEWALK CUTS, GUTTERS, AND DRIVEWAYS.

1. NOTIFICATION OF WORK:
   The Contractor shall call the City prior to starting any project. Telephone No. 394-8511.

2. ALL, repeat ALL lateral connections will be made by installation of a "Wye" (Y).

3. TRAFFIC CONTROL SAFETY AND WARNING DEVICES:
   The Contractor must provide barricades, signs and/or flagmen to secure work site during construction. Detours or other impediments to a normal flow of traffic shall have prior approval of the City Engineer or the Police Department.

4. BACKFILL AND COMPACTION:
   No backfilling will be commenced until the work has been inspected by a City official.

   Open cut trenches may be backfilled with materials excavated only with the approval of the City Engineer.

   Materials unsuitable for backfill must be disposed of by the Contractor and imported materials approved by the Street Superintendent shall be used.

   Backfill shall be compacted in lifts not exceeding six (6) inches, with air tamper, trench plate vib-compactor or other acceptable compaction methods.

5. CUTTING STREET SURFACES:
   All concrete and asphalt streets will be saw cut with smooth, straight edges.

6. UNCOMPLETED STREET OPENINGS:
   Where openings cannot be completed during the day of opening, suitable barriers shall be placed around the excavation to prevent accidents, and lighted barricades shall be continuously maintained at the opening site. Steel or wooden plates will be placed over trench if traffic would otherwise be impeded.

7. ARCHEOLOGICAL FINDS:
   In the event that any archeological finds (building ruins, utensils, tools, bones, etc.) are encountered, all excavating is to cease immediately and the City is to be notified.